

PACK BOY

MODULAR LIFTING SYSTEM FOR LONG PANEL PACKS



PACK BOY

Crane forks are self-levelling under all loads

Fully certified lifting slings are part of the standard kit

Standard kit contains all components, assembly tools and full certification



Modular compression beam can be assembled to desired length to suit pack dimensions

Fork opening heights are fully adjustable for high panel stacks

Technical specification and features -

- Standard kits suitable for packs up to 20m long and 4 tonne total weight
- Special kits for extended length panels and tandem lift options available
- Typical assembly time is 20 minutes for minimum two people with use of forklift or telehandler
- Transport size = 2m x 1.2m x 2m high
- Transport weight = 900Kg
- Fully assembled Pack Boy™ weight on crane = 650Kg (standard option)
- Each kit supplied with full certification and structural calculations
- Economical weekly or daily hire



Forks locate in wooden pallets below packs and prevent any panel damage

Modular form and unique storage container allows compact and economical transportation



Dublin Office

T + 353-(0)1-4519900

F + 353-(0)1-4519004

Cork Office

T + 353-(0)21-4342890

F + 353-(0)21-4342396

Tyrone Office

T + 44-(0)28-86758574

F + 44-(0)28-86758578

